

SCOPE OF WORK

DESCRIPTION OF PROJECT

Remove and dispose of two (2) existing entrance openings. Install new narrow style clear aluminum storefront entries: includes doors, sidelights, and transoms with "1/4" unisulated" clear tempered safety glass, hardware and locks. Install electric push button automatic openers at each door set.

DESCRIPTION OF WORK

A more detailed description of the accessible doors work to be undertaken at the location is as follows:

EAST ENTRANCE:

1. Remove existing pair of doors from frame, existing framing will remain.
2. Install new aluminum door set with continuous hinges, M/S lock, flush bolts, push-pulls and one overhead surface closer, and one automatic operator on other door.
3. Install wall mounted push button on exterior and interior of building.
4. Replace 4 existing sidelite glass panels with new safety glass panels.

WEST ENTRANCE:

1. Remove existing exterior storefront entry and replace with new complete. New doors to have offset pivots, M/S lock in active door, flush bolts in inactive door, push-pulls and overhead surface closer on one door. Install automatic closer on one exterior door and one existing interior door.
2. Install wall mounted push buttons on exterior and interior of building. One button set for the exterior door, and one button set for the interior lobby door.
3. Rework interior doors as needed to function properly.
4. Remove 4 existing wire glass sidelite panels on the interior and replace with safety glass.

SCOPE OF WORK
ACCESSIBLE DOORS PROJECT
RANTOUL BUSINESS CENTER
601 SOUTH CENTURY BLVD., RANTOUL, ILLINOIS

Prepared and Requested by:

Village of Rantoul
Community Development Department
Municipal Building
333 South Tanner Street
Rantoul, Illinois 61866

February 8, 2010